BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Extention of Major culvert at singapura main road near Ward office in Ward No. 11(Kuvempunagara) in Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	33.93	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable material with all lifts and lead and lead of 10000 meters complete as per specifications. lime/cement concrete, I.by manual means B. cement concrete grade M-15 & M-20 etc complete as per specifications and directions of engineer in charge of the work	Cum	382.32	Rupees Three Hundred Eighty Two and Thirty Two Paise Only
2	486.00	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in Hard soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	397.99	Rupees Three Hundred Ninety Seven and Ninety Nine Paise Only
3	54.68	Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, etc complete as per specifications and directions of engineer in charge of the work	Cum	2174.04	Rupees Two Thousand One Hundred Seventy Four and Four Paise Only
4	24.30	Providing and laying in position plain cement concrete of **mix 1:3:6 with OPC cement @ 220 Kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5236.92	Rupees Five Thousand Two Hundred Thirty Six and Ninety Two Paise Only

NIO & corrections - Nil

E.E. (BTP. DIV)

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	204.88	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete for R.C.C works laid in 15cms thick layers and well compacted vibrating curing etc. including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, column, Staircase and Roof with M-25 (1:1:2) (Cement - 399 Kg/Cum) etc complete as per specifications and directions of engineer in charge of the work	Cum	5236.92	#NAME?
6	20.49	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	59327.91	Rupees Fifty Nine Thousand Three Hundred Twenty Seven and Ninety One Paise Only
7	319.98	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface such as walls** at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	306.72	Rupees Three Hundred Six and Seventy Two Paise Only
8	202.50	Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) etc complete as per specifications and directions of engineer in charge of the work	Cum	311.04	Rupees Three Hundred Eleven and Four Paise Only
9	15.00	Providing and laying reinforced cement concrete pipe NP3 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications, 750 mm etc complete as per specifications and directions of engineer in charge of the work	M	4385.88	Rupees Four Thousand Three Hundred Eighty Five and Eighty Eight Paise Only

No corrections - Nil

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

07.01.17